

# Available Space - Colocation

**165** / HALSEY STREET

Location	Available	Electrical			Mechanical			Fire Protection	Telecom	BMS
		UTILITY	EPS	UPS	COOLING PLANT	COOLING DISTRIBUTION	CRAC UNITS			
<b>Colo Room III</b> 175 Cabinets 82 Cabinets	Immediate 12/1/15	N+1 spot network	N+1	N+1	N+1 (Chilled water)	Chilled water riser from roof to data center	N+1	Pre-Action	Direct to 9th floor MMR	Andover
<b>Colo Room IV</b> 608 Cabinets	9/1/15	Second continengy four (4) transformer spot network	N+1	2N	N+1 (Dry coolers)	Condenser water risers from roof to data center (2N risers & pumps)	N+1	Pre-Action	Direct to 9th Floor MMR	Siemens/ Automated Logic
<b>Colo Room V</b> 130 Cabinets	Immediate	Second continengy four (4) transformer spot network	N	3,600 amps -48V DC power	N+1 (Chilled water)	Chilled water riser from roof to data center	N+1	Pre-Action	Direct to 9th Floor MMR	Andover